Station Information:

Station	Easting (m)	Northing (m)	Level (m)
GH1	457839.677	337917.390	22.721
GH2	457769.706	337927.701	24.870
GH3	457779.379	337808.703	24.054
GH4	457761.688	337669.744	25.751
GH5	457824.195	337620.079	25.093
GH6	457887.752	337677.995	25.050
GH7	457924.158	337803.872	24.444
GH8	457912.536	337867.389	24.629
GH9	457871.296	337813.777	25.664

OS Note:

This survey has been orientated to the Ordnance Survey (O.S) National Grid OSGB36(15) via Global Navigation Satellite Systems (GNSS) and the O.S. Active Network (OS Net).

A true OSGB36 coordinate has been established near to the site centre via a transformation using the OSTN15GB & OSGM15GB transformation models.

The survey has been correlated to this point and a further one or more OSGB36 (15) points established to create a true O.S. bearing for angle orientation.

No scale factor has been applied to the survey therefore the coordinates shown are arbitrary & not true O.S. Coordinates which have a scale factor applied.

Please refer to Survey Station Table to enable establishment of the on-site grid and datum.

Legend:

Buildings, Wall, Kerb line, Line marking, Drop kerb, Centre line, Top of bank, Overhead Cable, Concrete edge, Tarmac edge, Grass verge, Canopy/Overhang, Verge, Bottom of bank, Station and Name, Station Level, Tree / Bush / Sapling, Area of Undergrowth, Woodland, R: Ridge Level, E: Eaves Level, F: Flat Roof Level, Gate

Fence types: IW Interwoven, IR Iron Railings, WM Wire Mesh, PR Post & Rail, PW Post & Wire, CL Chain Link, WP Wooden Panels, CB Close Boarded, SP Steel Palisade

IC Inspection chamber, Pinv Pipe invert, Gy Gully, Bg Back gully, Dp Down pipe, Pipe Pipe above ground, MH Manhole, WL Water level, Fl Flood light, Lp Lamp post, Tp Telegraph post, Ep Electricity post, Tl Traffic light, Bus Bus stop, Sv Stop valve, St Stop tap, Er Earth rod, Wm Water meter, Gas Gas valve, Av Air valve, ICU Unidentified inspection, Wo Wash out, Re Rodding eye, BB Bellsha beacon, CTV Cable tv, Mkr Marker post, Gmkr Gas marker post, So Soffit, Fh Fire hydrant

Bo Bollard, IB Illuminated bollard, Bin Rubbish bin, Vp Vent pipe, Grl Ground light, Lbox Letter box, Stmp Tree Stump, Sty Stile, IFL Internal floor level, THL Threshold level, Sp Sign post, TH Trialhole, BH Borehole, ELC Electric, BT British Telecom, C'box Control box, TT Tactile, BP Brick paved, CPS Concrete paving slabs, CVR Cover, R/wall Retaining wall, TWL Top of Wall Level, TCL Tree canopy level, G: Girth, MG Multi girth, IC Inspection chamber, CL: Cover level, IL: Invert level, UTL Unable to lift

Rev	Date	Description	Drawn	Q.

greenhatch group

- Topographical Surveys
- Site Engineering
- Utility / CCTV Surveys
- Measured Building Surve
- 3D Laser Scanning
- Revit & BIM Models

Rowan House
Duffield Road
Little Eaton
Derby
DE21 5DR
Tel (01332) 830044 Fax (01332) 830055
admin@greenhatch-group.co.uk
www.greenhatch-group.co.uk

St Albans: Unit B, The Courtyard, Alban Park, St Albans, Hertfordshire, AL4 0LA, t. (01727) 854481
Newcastle: 24 Riverside Studios, Amethyst Road, Newcastle Bus. Park, Newcastle-U-Tyne, NE4 7YL, t. (01912) 736391
London: 27, Cornwall Terrace, Regents Park, London, NW1 5LL, t. (02072) 2418

CLIENT

PROJECT
Victoria Embankment Garden
Nottingham,
NG2 2JS

TITLE
Topographical Survey

SCALE	DATE
A1@ 1: 500	
DRAWN: ER	QUALITY REF

Level datum	OS (see note)
Grid orientation	OS (see note)
Job number	37449
Drawing No.	37449_T
Re	0

Comments
This plan should only be used for its original purpose. Greenhatch Group accepts no responsibility for this plan if supplied to any party other than the original client.

All dimensions should be checked on site prior to design and construction.

Drainage information (where applicable) has been visually inspected from the surface and therefore should be treated as approximate only.

Notes:

©Copyright Greenhatch Group. 06/07/13